


Issue: Proposed hard surfacing located within the RPA of T3.  
Solution: Proposed surfacing to be designed in conjunction with an arboriculturist so that it can be constructed entirely above the existing soil level.

Issue: Proposed hard surfacing located within the RPA of T1, situated within the footprint of the existing decking.  
Solution: Proposed surfacing to be designed in conjunction with an arboriculturist so that it can be constructed entirely above the existing soil level.



Arboricultural Impacts	
Impacts	Nos. of trees
Trees to be removed	0
Groups / Hedges to be removed (Partial removal of groups)	0 (1)
Trees with proposed incursions into RPAs	2
Groups / Hedges with proposed incursions into RPAs	0
Trees that will require pruning	3
Groups / Hedges that will require pruning	1
Trees to be transplanted	0
Groups / Hedges to be transplanted	0

No.	Species	Proposed structure	Incursion
T1	Silver Birch	Hard surfacing	RPA
T3	Silver Birch	Hard surfacing	RPA

Arboricultural Impacts - RPAs (Area)				
No.	Species	RPA (m <sup>2</sup> )	Incursion (m <sup>2</sup> )	Ratio
T1	Silver Birch	1.4	1	0.71
T3	Silver Birch	6.5	0.34	0.2

Tree Work Schedule				
No.	Species	Works	Category	
T1	Silver Birch	Prune to facilitate demolition and construction access	C1	
T3	Silver Birch	Prune to facilitate demolition access	C1	
T4	Silver Birch	Prune to facilitate demolition access	C1	
G1	Various	Prune to facilitate installation of footpath	C2	
G2	Various	Prune, overhanging foliage to achieve 2m clearance from the existing building / highway	B12	
G4	Various	Partial full section section as shown on the AIA site, aerial photos	C2	

All tree work is to be undertaken in accordance with British Standard BS 3998:2010 Tree work - Recommendations.  
All existing trees to be removed and the site is to be left as found.  
Care is to be taken of the ground around retained trees to make sure that it does not become compacted as a result of tree surgery operations. No equipment or vehicles such as timber forklifts, tractors, excavators or cranes shall be parked or driven beneath the crowns of any retained trees, to prevent subsequent compaction and root death.

No. of individual trees to be removed				
U	A	B	C	
0	0	0	0	0

No. of groups / hedges to be removed				
U	A	B	C	
0 (0)	0 (0)	0 (0)	0 (1)	

(1) Partial removal of a group

**'No Dig' Surfacing**  
Trees can be affected by construction within the RPAs either through the direct damage caused by the removal of roots, compaction of the rooting environment or secondary damage such as poisoning through leaks and spills (oil, fuels, etc) or through desiccation (road salt, etc).  
Proposed hard surfacing within the RPAs of retained trees is to be designed so that it can be situated above the existing soil level and to minimise any adverse impact upon the tree RPAs, as the use of traditional foundations can result in excessive root loss through direct removal of roots during excavation and by compaction of the soil beneath the excavation, as such this 'traditional' type of foundation should be avoided.  
When designing hard surfacing that is to be situated within RPAs, the design team need to pay particular attention to the proposed design (pedestrian, domestic traffic, delivery vans, Emergency vehicles, HGVs etc.), the existing and proposed levels of hard surfacing and finished floor levels, edging types and details, proximity to tree trunks and surface rooting, contamination capture, SUDs, etc.

Possible sub-bases (foundations systems) for hard surfacing situated within the RPAs of retained trees could include:  
• A proprietary system such as a multi-dimensional confinement system (Calfweb TRP or similar).  
• Engineered solution such as a road deck, bridge, etc.  
An engineered solution is likely require a level of excavation for site specific investigations to locate roots to aid in foundation design so that a suitable foundation can be designed to avoid roots and for the installation the structure.  
NB. The use of a multi-dimensional confinement systems and or an engineered solution will affect the finished level of the hard surfacing by raising the levels and needs to be taken into consideration when designing foundations and setting the finished floor levels of adjacent buildings.

**Utility apparatus**  
Underground utility apparatus  
Mechanical trenching for the installation of underground apparatus and drainage services any roots present and can change the local hydrology in a way that adversely affects the health of the tree. For this reason, particular care should be taken in the root and methods of installation of all underground apparatus. Wherever possible, apparatus should be routed outside of RPAs. Where this is not possible, it is preferable to keep apparatus together in common ducts, all inspection chambers should be sited outside of the RPAs.  
Where underground apparatus is to pass within the RPAs, detailed plans showing the proposed route should be drawn up in conjunction with the project arboriculturist. In such cases trenchless insertion methods should be used with entry and retrieval pits being located outside of the RPAs. If this option is not feasible and providing roots can be retained and protected excavations should be undertaken using hand held tools (air-spade, forks, shovels) or a combination of trenchless and manual excavation (broken trench).  
Any design and installation should be undertaken in accordance with the National Joint Utilities Guidelines (NJUG).

Above-ground utility apparatus  
Above-ground apparatus including CCTV cameras and lighting should be sited to avoid the need for detrimental tree pruning, as such the current and future crown size of the tree should be assessed.  
Tree branches can be pruned back with care to provide space, though it is not appropriate for repetitive and significant tree work to be seen in the design solution unless this is a suitable management outcome for the tree. Any pruning should be undertaken in accordance with BS3998:2010

**Arboricultural Method Statement**  
All tree work is to be undertaken in accordance with British Standard BS3998:2010  
Please refer to Arbtach Consulting Ltd. Tree Schedule, Arboricultural Method Statement and Tree Protection Plan for full details of all surveyed trees and how all aspects of the development may be implemented without detriment to retained trees.

**Arboricultural Method Statement**  
All tree work is to be undertaken in accordance with British Standard BS3998:2010  
Please refer to Arbtach Consulting Ltd. Tree Schedule, Arboricultural Method Statement and Tree Protection Plan for full details of all surveyed trees and how all aspects of the development may be implemented without detriment to retained trees.

Rev: Date: Notes:  
A 12.08.24 Updated with latest layout.



Project: Premier Inn, Llanelli Central East, Llanelli, SA14 9BD  
Client: Premier Inn Hotels- Llanelli Central East

Drawing: Arboricultural Impact Assessment  
Based on: 6127-P-010-D

Drawing No: Arbtach AIA 01  
Date: Jul 2024  
Scale: 1:200 @ A0  
Rev: A  
Drawn: EK

Key:				
Tree Nos.	T1	Tree Categories	Thunks	
RPAs	Category 'B' groups	Category 'C' trees		
Category 'C' groups	Existing Site (Foot)	Proposed Site		
Trees to be removed	d4	Incursion - Hard Surfacing		

